

Design, Construction, and Actual Performance of Prefabricated Wooden Houses

Yuxiang Chen, Ph.D. P.Eng

Associate Professor

Department of Civil and Environmental Engineering

University of Alberta

E-mail: yuxiang.chen@ualberta.ca



UNIVERSITY OF
ALBERTA

“uplifting the whole people”

— HENRY MARSHALL TORY, FOUNDING PRESIDENT, 1908

February 12, 2024


Outline

- Introduction
- Design & construction
 - House, energy & mechanical systems
- Monitored performance
 - Thermal performance
 - Energy analysis
- Mass-Timber-Panel Basement
- Conclusion

Introduction

■ Energy consumption for space heating/cooling


■ > 21% of the national energy consumption



* PJ = 2.8E8 kWh

Introduction

■ Peak electricity demand




■ Demand and supply mismatch (amount, time)

Introduction

- Improved load profile
 - Low energy consumption
 - Energy efficiency measures
 - Reduce and shift peak demand
 - Active thermal energy storage (TES)

Winter space heating demand profile



Introduction


■ Utilization of ambient renewable energy

■ Solar energy

- Passive solar heating

- Solar thermal collector & PV

■ Geothermal



Introduction

■ Building Integrated Photovoltaic/Thermal (BIPV/T) system

■ Significantly increase overall efficiency


■ Higher efficiency

of electricity ξ

■ Collect thermal energy

■ Enhance architectural appeal

■ Reduce overall energy consumption




Introduction

■ Ventilated Concrete Slab (VCS)

■ Thermal energy storage

- Suitable thermophysical properties
- Active thermal mass
- Large quantity

■ Assist space heating/cooling



Background

- CMHC* EQuilibrium (2006 ~ 2010)
 - One of the winning projects nationally
- Single family, detached house in Eastman, Quebec, Canada
 - 210 m² (two-story with a semi-basement)
- Construction finished in Nov. 2007
- Occupied since August 2009
- Important research project of several groups
 - SNEBRN, Hydro Québec, NRCan, CMHC, IEA
 - Case study of IEA task 40 “nZEB”
- Demonstration & public education



Design & Construction

Key Design Features

■ High performance envelope

- Thermal insulation: Walls: RSI 6.4 (R 36);
Roof: RSI 9.3 to 10.9 (53 to 62)
 - Structure integrity and acoustic insulation
- Air-tightness: < 0.1 air change per hour

Key Design Features


■ Building-integrated photovoltaic & thermal system (BIPV/T)

- Electricity generation
- Thermal energy collection
- DHW heating
- Drying clothes

■ Ventilated concrete slab

- Active thermal energy storage
 - Assist space cooling/heating

~ 30 m², 5 m³, 3 kWh/K



Key Design Features

■ Passive Solar Heating



- Large south-facing windows
- Significant thermal mass (concrete slab & walls)
- Motorized blinds

■ Geothermal HP


- Heating/Cooling
- Partial DHW heating

■ Heat recovery ventilation

■ Automation system



Key Design Features




**2.8 kW
BIPV/T**


**Passive Solar
Heating**

**South window
area to floor
area: 11%**

Key Design Features



Building-Integrated Photovoltaic & Thermal (BIPV/T) System



ÉcoTerra

■ Thermal insulation

- Two types/layers of insulation for the envelope



Basement



Above grade

ÉcoTerra

■ Pre-fabrication

Floor
+
Ducting



Walls and
Partitions


One
Module



Spray
Insulations

ÉcoTerra

■ On-site assembly of modules



ÉcoTerra

■ Built Environment

Family Room



Study Room
&
Basement (VCS)

Mechanical System



Monitoring


Thermal and Energy Performance

PV Electrical Performance

■ Modeled: 3265 kWh/yr


■ Monitored: 2570 kWh/yr

■ Winter snow accumulation effect




BIPV/T - cold sunny day

■ Thermal energy collected: 9.5 kW @ 12:00



BIPV/T

- Hot summer days (infrared image)




June 22th, 2008

House and VCS


■ Passive solar heating & VCS (cold sunny day)

Heating was needed during the night time, less than 4 hrs/day



Energy performance


■ Annual Consumption by End-Use



ÉcoTerra

10,318 kWh/year

49 kWh/m²/yr (156 kWh/m²/yr for Québec)



Average Single-Family Detached Home in Canada

38,389 kWh/year

(Matt Doiron, 2011)

Design vs. Actual




(a) Before occupied



(b) Occupied

Energy Performance

■ Annual Consumption by End-Use




(Matt Doiron, 2011)

Cross-Laminate Timber (CLT) Basement Walls




Cross-Laminate Timber (CLT) Basement Walls



Plan View
SCALE: 1:50

EXCAVATION PLAN VIEW


Cross-Laminate Timber (CLT) Basement Walls



Cross-Laminate Timber (CLT) Basement Walls


Effective thermal resistances

Exterior water proof membrane
3/4" XPS continuous insulation
3-ply CLT panel
2x4@16" stud with cavity thermal insulation
Cavity insulation
Vapor barrier
Interior gypsum board and paint



Nominal RSI is 3.7, effective RSI is about 3.3 (R 18.9).

Exterior water proof membrane
3-ply CLT panel
2x6@16" stud with cavity thermal insulation
Cavity insulation
Vapor barrier
Interior gypsum board and paint



Nominal RSI is 4.5, effective RSI is about 3.9 (R 22).

Code requirement: RSI 2.98 (R 17.5). Both configurations pass condensation tests.


Cross-Laminate Timber (CLT) Basement Walls



Cross-Laminate Timber (CLT) Basement Walls




Cross-Laminate Timber (CLT) Basement Walls




Cross-Laminate Timber (CLT) Basement Walls

Effective thermal resistances


- M Moisture content (4)
- R Relative humidity (12+1)
- II Temperature (16+1)




Code requirement: RSI 2.98 (R 17.5). This configuration passes a condensation test.



Cross-Laminate Timber (CLT) Basement Walls



Relative Humidity



Conclusions

- A low-energy solar home is designed, built, and assessed.
 - It integrates innovative and conventional systems
 - The energy consumption is 25% of the national average, but with potential of less than 20%.
- Low-energy design enhances energy efficiency
- Occupant factors

Questions /
comments ?